

FEB 18 1994

**CLARE COUNTY REMONUMENTATION PROGRAM**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

DEC 20 PM 1:43

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>4W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1856 G.E. ADAIR, POST, W.OAK 4" N 19°W, 16 LKS P.370  
 W. OAK 5" S 81-3/4°E, 28 LKS  
 9-7-13 A. JOHNSON, PINE 24" S 53°E, 44 LKS CSR 1-31  
 5-2-72 LAPHAM, LCRC 33-72  
 10-2-72 LAPHAM, LCRC 63-72  
 9-27-84 LAPHAM, LCRC 479-85

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NAIL & R.L.S. TAG IN ASPHALT OVER CONCRETE PAVEMENT.  
 FOUND RECORDED WITNESSES:  
 WEST, 100.00' - CONC. MONUMENT  
 N 70°W, 87.5' - N.E. COR. CONC. BLOCK GARAGE  
 N 87°E, 57.10' - 18" OAK (32" OAK FITS BEARING & DIST)  
 S 40°W, 75.24' - 15" OAK

SET 2 REFERENCE POINTS (1/2" x 18" L.L.S. CAPPED IRON) 20.00' EAST & WEST OF NAIL & R.L.S. TAG

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND NAIL & R.L.S. TAG IN ASPHALT, SET REFERENCE POINTS 20.00' EAST & WEST  
 S 45°W, 74.9' - 24" OAK (TWIN)  
 N 25°W, 150.35' - POWER POLE  
 N 50°E, 80.85' - 20" OAK  
 N 85°E, 56.72' - 32" OAK



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458