

FEB 18 1994

COMMISSION

CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 20 PM 1:43
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For comers in

CLARE <small>(County)</small>	Located In:	Corner Code =#
1. Public Land Survey	T <u>20N</u> R <u>4W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1856 G.E. ADAIR, CEDAR 9" N 61°W, 35 LKS P.426
 CEDAR 13" S 10°E, 19-1/2 LKS
 5-5-72 LAPHAM, MON. BOX 6.45' W. OF C LCRC 33-72
 8-20-75 LAPHAM, FOUND MON. BOX LCRC 216-75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" IRON IN MONUMENT BOX 5-1/2 FEET WEST OF C U.S. 27 PAVEMENT. EXCAVATED TO 3' DEPTH,
 FOUND NO OTHER EVIDENCE.
 FOUND RECORDED WITNESSES:
 EAST, 6.45' - CENTERLINE OF HIGHWAY
 WEST, 54.95' - CONC. R/W MONUMENT (FOUND MON. IN SWAMP @53-1/2', LEANING BADLY.

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 WEST, 41.60' - 14" ELM
 N 25°W, 114.67' - POWER POLE
 N 40°E, 131.60' - POWER POLE
 S 20°E, 85.00' - 12" ELM
 EAST, 6.50' - CENTERLINE, HIGHWAY

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458