

CLARE County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 #282-98  
 98 NOV 18 AM 9 50

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R04W	H-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. MAULAY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on June 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
				18		17		16		15		14	
8				19		20		21		22		23	
9													
10				30		29		28		27		26	
11													
12				31		32		33		34		35	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-7: 1856 Adair GLO  
Set 1/4 Sec Post  
Wit-Hemlock 10 N35W 13  
Beech 9 S35E 30  
11-06-86 Lapham (132) 3-35  
Wit-same as (132) 2-375
- 6-09-77 Lapham (132) 2-375  
Set 1/2" C.I. Notes state Cor Set from 1970 witnesses of surveyer McComb  
Wit-N45W 27.54 Tw. Oak  
N60E 61.32 18" Maple  
S20W 46.05 16" Oak  
S40E 55.60 14" Oak  
Meas 2643.46 West & 2645.81 East to Sec Cor
- 11-20-78 Lapham LCRC#320  
Wit-same as (132) 2-375

**SURVEY &  
 REMONUMENTATION**

NOV 25 1998

SECTION

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- H-7: Found 1/2" x 18" Rerod and all 1977 witnesses. Recorded West 2643.46 to G-7. Excavated and found no other material.
- See dossier for detailed report.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- H-7: Set 5/8" x 36" rerod with Clare Co. Remon. Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 N40W 27.54', nail & tag, Twin 10x13 Red Oak (OBT)  
 S20W 46.05', nail & tag, Twin 24x16 Red Oak (OBT)  
 S43E 55.60', nail & tag, 22" Red Oak (OBT)  
 N28E 26.84', nail & tag, 14" Maple Clump of 3



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul S. Leph  
 Date 9-22-98

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-16-98