

SURVEY & REMONUMENTATION

JAN 14 1999

CLARE County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in

| | | |
|------------------------------------|-------------|---------------|
| CLARE (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T20N R04W | I-7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

#305-98
98 NOV 24 AM 10:23

REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McAULAY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

1/30/79 Sedgman, LCRC #335
same wits as (132) 2-400. Found T-iron, raised grade with 1/2" iron bar.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7: 1857 Adair, GLO
Set post Sec 14-15-22-23
Cedar 8 N53E 21
Tamarack 12 S08W 9
- 3/14/57 Moore, CSR 3-64
notes he found corner, no wits
- circa 1900, Unknown, CSR 5-266
Hemlock 6 S33W 31
- 6/9/75 A.S. Pierson, (132) 2-46
Found T-iron, no wits. meas. East 1323.66 feet to 1/8 corner.
- circa 1900, Unknow, CSR 5-275
Cedar 8 N53E 21
- Undated, PBL files
Found T-iron; Meas. West 2646.31 to H-7
- 4/10/07 Johnson, CSR 4-92
Hemlock 6" S33W 31
- 9/26/78 Sedgman, (132) 2-400
Fd. T-iron (Rec. South 2715.04 to I-8)
South 3459 N.E. Cor. Stone Mon.
N80W 98.31 14" Hemlock
N70E 76.31' 6" Hemlock
- 4/28/09 Johnson, CSR 4-158
Cedar 8" N53E 21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7: Found 1/2"x18" re-rod over 24" T-iron. Found two 1978 witnesses. Meas. West 2644.76 feet to H-7. Meas. East 2647.30 feet to J-7.

See dossier for detailed information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7: Set 5/8"x36" re-rod with Clare Co. remon cap marked PS 27458. Accepted as best available evidence of the accepted position of the corner.
S40E 55.30 Nail & Tag in PP
S46W 56.28 Nail & Tag in 11" Maple
N72W 98.31 Nail & Tag in 16" Tamarack (OBT)
South 34.59 N.E. Cor. Stone monument (OBT)



APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Topham
Date 10-20-98

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-23-98