

FEB 18 1994

**CLARE COUNTY REMONUMENTATION PROGRAM**

RECEIVED

1993 DEC 20 PM 1:43

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 4W	1-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1856 G.E. ADAIR, Y. PINE 16" N 61°W, 89 LKS P.421  
 Y. PINE 13" S 52°E, 26 LKS  
 5-5-55 W. MOORE, 10" OAK N 34-1/2°W, 59.8' CSR 3-28  
 12" OAK S 68-1/2°E, 53.1'  
 12" OAK S 82-1/2°W, 42.7'  
 11-11-55 W. MOORE CSR 3-44  
 8-9-56 W. MOORE CSR 3-49  
 3-14-57 W. MOORE CSR 3-64  
 11-06-73 LAPHAM, WITNESSES AS CSR 3-28 LCRC 124-73  
 2-1-79 LAPHAM, (132) 2-429

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" RE-BAR (POINTED) OVER 3/4" PIPE IN NEST OF CONCRETED STONE W/ ONE VERY LARGE POINTED STONE ON EAST EDGE OF CORNER. EXCAVATED HOLE AROUND CONCRETE & STONE MONUMENT. REMOVED 3/4" PIPE  
 FOUND RECORDED WITNESSES:  
 S 82°W, 42.7' - FACE OF 30" STUMP  
 N 60°W, 46.65' - CENTER, 18" OAK  
 S 40°W, 30.91' - CENTER, 12" OAK

This Corner established in Clare County Remonumentation Program.  
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.  
 S 82°W, 50.00 N.E. CORNER, GARAGE  
 N 60°W, 46.65' - 20" OAK  
 S 60°E, 77.9' - 18" OAK  
 S 20°E, 78.8' - 18" OAK



Signed by [Signature]

Date 11/24/93

Surveyor's Michigan License No. 27458