

FEB 18 1994

COMMISSION

CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E O I O A O
 1993 DEC 20 PM 1:43

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>4W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1856 G.E. ADAIR, HEMLOCK 12" N 48°W, 36 LKS P. 419
 HEMLOCK 10" S 60°E, 21 LKS
 1-10-57 W.S. MOORE, SET IRON 5243.7' EAST OF N.W. CORNER, CSR 3-58
 SECTION 34 & 43.7' EAST OF FENCE
 9-2-82 K. OSTLING, FOUND 1/2" ROD LCRC 423-82

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" IRON AT THE CORNER WITNESSED IN LCRC 423-82. ALSO FOUND 1/2" IRON 43' WEST. THIS IRON WAS MARKED AT THE SURFACE WITH A CABIN SPIKE AND NAIL. NO OTHER EVIDENCE WAS FOUND. EXCAVATED CORNER WITNESSED IN LCRC 423-82, FOUND NO OTHER EVIDENCE.
 FOUND RECORDED WITNESSES:
 S 34°W, 28.6' - 4" R. MAPLE
 WEST, 28' - @ "T" ROAD, SOUTH
 WEST, 43' - 1/2" IRON

MOORE STATED HE SET CORNER G.L.O. DISTANCE (5243.7') EAST OF 27-28-33-34 SECTION CORNER. MEASURED 5240.7'. OSTLING USED AND RECORDED THIS CORNER AND STATED THAT IT WAS USED IN PREVIOUS SECTION SUBDIVISIONS. OSTLING WAS THE D.N.R. SURVEYOR AND USUALLY SPENT CONSIDERABLE TIME TO DETERMINE THE VALIDITY OF HIS SURVEYS. IT IS MY OPINION THAT THIS LOCATION IS THE BEST LOCATION FOR THIS CORNER.

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 N 70°W, 47.52' - POWER POLE
 N 10°E, 58.36' - 10" OAK
 S 30°E, 58.36' - 6" TWIN OAK
 S 55°W, 71.22' - 15" MAPLE
 WEST, 42.92' - 1/2" IRON



Signed by Mark R. Robison Date 11/24/93
 Surveyor's Michigan License No. 27458