

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REC'D
 #297-98
 98 NOV 24 AM 10:22
 REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. MAULAY

For corners in

CLARE Located in: Corner Code #
 (County)

1. Public Land Survey T20N R04W J-13 ✓
 T19NR04W J-1
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on October, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

This is a single corner common to
 T20N, R04W, J-13 and T19N, R04W, J-1

- A. Description of original monument and accessories and/or subsequent restoration:
- J-13: 1838 Nicholson, GLO
 Set 1/4 Sec. Post on West bank of lake
 Aspen 6- S29E 14
 Aspen 8- N37-1/2W 28
 - 8/22/58 Moore, 5-23; Plat of Red-Woods Resort
 References W 1/8 Cor of Sec. 35
 - 6/14/56 F. McClung, CSR 3-88
 Plat Mon - No Witnesses, I-J 2804, J-K 2612.8
 - 6/26/46 Spicer, 2-25; Ref. in Plat of Hiram Hills
 - 11-06-57 Moore, 5-16; Plat of Red Man-Woods Resort. S.E. Cor. of Plat (Plat Mon)
 - 2/14/74 Lapham, LCRC 145
 Found Monument
 N05W 13.86 8" maple
 N60W 13.20 8" Maple
 S45W 3.91 8" Maple
 - 4/1/74, Meyers, (132) 1-683
 Found Concrete monument being the SE Cor. of Lot 1, Red Man-Woods Resort
 - 6/27/75 Lapham, (132) 2-3
 S1/4 Cor. Sec. 35 as rec. in LCRC #145 records
 W1/2 of SW1/4, Sec. 35 at 1401.67

**SURVEY &
 REMONUMENTATION**
 JAN 14 1999
 SECTION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J-13: Found Concrete moonument with 1-1/4" pipe in center & 3/4"X30" pipe in 1-1/4" pipe. Found all 1974 witnesses. Meas. West 2804 (Sub-meter) (McClung 2804 in CSR) to I-13.

See dossier for detailed information.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-13: Set 5/8"X36" re-rod with Clare Co. remon cap mark PS 27458. Accepted as best available evidence of the accepted position of the corner.

N18W 13.20 Nail & Tag in 12" Maple (OBT)
 N70W 12.30 Nail & Tag in 12" Maple (OBT)
 S68W 3.19 Nail & Tag in 10" Maple (OBT)
 S12W 26.25 Nail & Tag in 12" Maple



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul S. Lapham
 Date 10-20-98

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-23-98