

**SURVEY & REMONUMENTATION**

JAN 14 1999

CLARE County Remonumentation

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R04W	K-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED  
#303-98  
98 NOV 24 AM 10:23  
REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. HEAULAY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

- A. Description of original monument and accessories and/or subsequent restoration:
- K-7: 1856 Adair; GLO; Set Post cor Sec 13,14,23,24  
Maple 18 corner  
Hemlock 30. N49W 50  
Birch 22 S25E 14  
7/13/74 Fraus (132) 1-189  
Division of N1/2 Section 23  
Meas 2640.56 West to J-7  
Meas 2630.62 South to K-8
  - 4/10/07 Johnson; CSR4-92 & 5-266  
Birch 4 S36E 18  
K-7 to J-7 40.15
  - 4/28/09 Johnson; CSR 4-158 & 5-275  
W. Pine 60 SW 68
  - 12-10-57 W.S.Moore ; CSR 3-81482  
24" Pine N30W 39.8  
8" Maple S 45.7

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-7: Found Capped iron in 1-1/2" X13" pipe at corner. Measured West 2640.53 (Fraus 2640.56) to J-7. Found & disregarded 3/4" pinch pipe N68W 11.38' and 1-1/2" pipe East 31.44'. Measured East 2647.66 feet to L-7. Found one 1957 witness

See dossier for detailed information

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-7: Set 5/8" x 36" rod with Clare Co. Remon. Cap marked P.S.#27458 in Monument Box. Accepted as best available evidence of the accepted position of the corner.

N10E 76.92' N&T in 34" Maple  
S08W 38.16 pipe  
N40W 40.35' N&T in 32" W. Pine (OBT)  
North 43.50' N&T in 22" Maple



**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Lopham  
Date 10-20-98

Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 11-23-98