

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <u>●</u> R. <u>4</u> W. <u>●</u>	A-3; A-4; A-5; B-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 15, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-3 Found T-iron (possibly old sign post) at road intersection; origin unknown.
- A-4 Set by proportionate measurement, midpoint on line, between section corners. Could locate no previous corner.
- A-5 Found ½" iron bar, origin unknown, that seems to fit occupation in Sec. 7. Probably established in connection with gravel pit but can find no record of same.
- B-3 Found ½" iron bar, placed by unknown. Also found another piece of iron about 1.8' south and 1.8' east of bar. Unable to determine a predominant validity, so used iron bar, which was probably set for most recent survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	A-4	A-5
Left T-iron in place	Set DNR monument	Set DNR monument & red-top post
10" J. Pine N18°E 36.0	10" Oak N45°E 64.7	5" J. Pine S80°W 21.6
6" Oak S15°E 82.3	6" Oak N80°E 118.3	6" J. Pine S43°E 10.1
B-3		
Left ½" iron bar in place		
12" J. Pine S50°W 61.6		
6" R. Pine S30°E 61.5		

SIGNED BY *Kenneth J. Ostling* DATE 1-9-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

