

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. R. <u>4</u> W.	<u>B-4; B-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>20</u> N. R. <u>4</u> W.	<u>11; 14; 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 12, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

	14	15
	Set ½" iron bar	Set 3' of 1½" pipe & red-top post
	6" Oak N85°W 50.6	6" W. Oak N64°E 39.2
	3" Maple N30°W 44.4	12" R. Oak N18°E 4.3


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-4 Established at computed intersection of true ¼ lines as prescribed by standard survey procedure.
- B-5 Set corner by proportionate measurement between section corners. Falls in line with old fence line north.
- 11 Set by standard survey procedure for the subdivision of sections.
- 14 Set by standard survey procedure for the subdivision of sections.
- 15 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-4	B-5	11
Set 1½" pipe & red-top post	Set DNR mon. & red-top post	Set 3' of 1½" pipe & red-top post
5" W. Oak N07°E 7.5	4" W. Oak N06°W 29.8	12" R. Oak S05°E 21.9
10" Twn.W.Oak S50°E 28.1	6" W. Oak N49°W 50.1	3" R. Pine S60°W 27.0
	22" R. Oak S83°W 7.0	

SIGNED BY Kenneth J. Ostling DATE 1-9-76
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____