

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u>	Located In:	Corner Code \neq
(County)		
1. Public Land Survey	T <u>20N</u> R <u>4W</u>	<u>A-2</u>
	T _____ R _____	<u>A-3</u>
	T _____ R _____	<u>B-2</u>
	T _____ R _____	<u>B-3</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL F. ROSER, in a field survey on JUNE 22, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2 A-3 B-2 B-3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 ACCEPTED FD RLS PAUL LAPHAM 1/2" REROD FOR 1/4 COR COMMON TO S-6 (T20N-R4W) & SEC. 1 (T20N-R5W). LAPHAM HERE IN 1983 FOR SUR OF S-1, T20N-R5W.	A-3 FD OLD STEEL FN POST IR AS RECOVERED AND ACCPETED BY RLS KEN OSTLING IN 1976; IN HIS SURVEY OF SEC. 7, T20N-R4W.	B-2 ESTAB CTR OF S-6 AT INTERSEC OF ONE-QUARTER LINES. SINGLE STRAND SMOOTH WIRE (N-6, VERY CROOKED) IN TREES IS 180'±20' WEST. N-6 SAND TRAIL IS 380' ±20' WEST.	B-3 FD PREV DEPT COR OF RECORD; RLS KEN OSTLING FD 1/2" IRON ROD HERE IN 1976. COR FALLS IN CTR OF E-W GRAVEL ROAD. TRAIL ROAD SOUTH IS 130' WEST.
--	--	---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 FD 1/2" REROD W/RLS CAP #9433; REPL W/DNR NOM & SET CED POST. 12" R PINE N34°W 6.1' 12" TM OAK N30°E 11.6' *10" R PINE N82°E 16.5' 9" R PINE S20°W 26.5'	A-3 FD OLD FN POST IR & REPL W/ 5/8" X 3/4" REROD W/RLS CAP. 16" OAK N34°W 69.5' 14" R PINE N18°W 48.5' 14" OAK N20°E 73.19' 10" TM OAK S16°E 82.27' 10" OAK S20°W 55.95'	B-2 DROVE 5/8" X 3/4" REROD W/RLS CAP & SET CED POST W/LOC TAG. 15" OAK S58°E 12.5' 8" OAK S70°W 11.0' 12" OAK N52°W 12.4' 11" OAK N56°E 9.3'	B-3 FD 1/2" IR ROD; REPL W/ 5/8" X 3/4" REROD W/RLS CAP. *11" RED PINE S32°E 61.3' *12" J PINE S48°W 61.3' 11" OAK N30°E 56.9' 26" OAK N56°E 57.7'
* PBL NITS.	SET CED POST W/ LOC TAG. NORTH 33'		SET CED POST W/ LOC TAG SOUTH 30'±

*KJD NITS.

Signed by Carl F. Roser 11-14-91 Date _____
 Surveyor's Michigan License No. 12028

