

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 (County) _____

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S 24 _____	T 20N _____	R 4W _____
	S 24 _____	T 20N _____	R 4W _____
			SN 1/64 _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on Sept. 9, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number _____

A. Description of original monument and accessories and/or subsequent restoration: SN 1/64 - None
 Z - "Frosty Acres Sub" - L. 11 of plats, p. 5 & 6 -
 M. McClung - 1969 - Shows Conc. Mon. 33.01' W. of corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Z - N 1/16 Cor. Common to Sec. 24, T20N, R4W and SN 1/64 - Corner common to Sec. 24, T20N, R4W and Sec. 19, T20N, R3W - Set 2" Alum. Cap on the N 1/2 of SE 1/4 of NE 1/4 Sec. 24 - 5/8" x 3/4" iron rebar per standard BLM procedure in CL. N-S Gravel Rd.
 Set 2" Alum. Cap on 5/8" x 3/4" iron rebar in CL. N-S Gravel Rd. per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Z - 2" AC on 5/8" x 3/4" Rebar SN 1/64 - 2" Alum. Cap on 5/8" x 3/4" Rebar
 S88° 44'W 33.24' (33.01' - P) to Fd. Conc. S88° 51' W 32.97' to Fd. 5/8" CIR #13037 & add blue carsonite post w/ Loc. tag
 Plat mon. and add blue carsonite post w/ Loc. tag S86° 23'E 32.74' to Fd. 1/2" CIR #27458
 S79°E 53.44' to set N & T in N side UP N62°W 28.49' to set N & T in NE side 6" Oak
 N54°E 121.85' to NW Cor. Blk. Frndt. Hse. #8800. N33°W 67.46' to set N & T in SW side 3" Oak

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003

