

MAR 24 2000

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>B-5</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

199900007870
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 34 - 34

Instrument Liber Page
199900007870 OR 2 34

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
Set 1/4 Sec Post
S. Pine 6" N24W 30 Lks.
S. Pine 6" S52E 27 Lks.

1914 Johnson, CSR 6-116
Oak 10 N66-30E 155 Lks.
Oak 8 S13E 86 Lks.

1933 Johnson, CSR, 2-51
Same as CSR 6-116

5-22-92 Roser, LCRC, #688
Re-established S1/4 of Sec. 7 at proportionate meas. to U.S. (GLO run out Sec) & on line btwn. fd Sec Cors 1/2 mi. E & W Ctr. of 29' wide E-W Gravel Rd is 12' North. Drove 5/8" x 34" re-rod w/RLS cap. S10°E 45.5 18" B. Oak (in clp). S20W 94.5 4" B. Oak S70W 139.7 8" Tw. B. Oak North 45' ced. post w/loc. Tag

3-29-94 Roser, DNR Plan No. R-18-AB
Meas. S89-49-17W, 2403.57 to DNR Mon
Meas. N89-49-17 E, 2638.43 to C-5

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman *Paul D. Lyle*
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.

Fd C.F. Roser Cap or 5/8" x 34" re-rod 12' S. of C.L. Gravel Road. Fd stump of one witness and the D.N.R. Post.

Accepted as the best available evidence of the position of the original corner and replaced with Standard Monument Corner. C-13 was approved for remonumentation at a Peer Review Committee meeting

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Clare Co. Remon cap marked P.S. #27458 on existing 5/8" x 34" re-rod. Corner position is accepted method of re-establishment of the corner.

Witnesses:
North 44.86 Set N & T in D.N.R. Post (OBT)
N30E 50.33 Set N & T in 3" J. Pine
S14E 46.30 Set N & T in Cen 24" Oak Stump (OBT)
N30W 57.30 Set N & T in 4" J. Pine

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458



Date 9-15-99