

REMONUMENTATION

NOV 18 1997

COMMISSION

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

#206-97
97 OCT 15 AM 10:50

REGISTER OF DEEDS
CLARE COUNTY
CAROL A. MAULAY

SUMMERFIELD
GREENWOOD

Register of Deeds Stamp & File Number

For corners in

CLARE
(County)

Located in:

Corner Code #

1. Public Land Survey

T20N R 5W

B-13

T19N R 5W

B-1

T R

T R

S T R

S T R

S T R

S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson
Set 1/4 Sec Post
Wit-P. Pine 18" N56W 30
W. Pine 26" N89 1/2E 43

8-10-92 Roser LCRC#702
Fd Pipe by M. Schaaf 1941. Schaaf set
Pipe from W. Pine Stp. remains NE with
"Portions of lower face plainly visible"
that he says was G.L.O. Added D.N.R.
Mon & set Ced. Post
Wit-2" W. Pine N15W 9.6'
2" W. Pine N35E 28.7'
3" W. Pine S75E 11.8'
10" B. Oak S60W 20.3'

No CSR records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found D.N.R. Monument and witnesses and remains of GLO 26" Pine stump.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul B. Poplar

Date 9-23-97

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted D.N.R. Monument as Clare County Remonumentation Monument. Accepted as perpetuation of original corner.

Witnesses:

N15W 9.60', N&T, 3" W. Pine (OBT)
N35E 28.70', N&T, 3" W. Pine (OBT)
S75E 11.80', N&T, 4" W. Pine (OBT)
S60W 20.30', N&T, 12" B. Oak (OBT)

Signed by

Mark R. Robison

Surveyor's Michigan License No. 27458

Date

10-01-97

