

**SURVEY &
REMONUMENTATION**

JAN 23 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>20N</u> R. <u>5W</u> | <u>C-9</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

200000010165
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-15-2000 At 07:44 am.
LAND CORNER 9.00
OR Liber 2 Page 288 - 288

Instrument Liber Page
200000010165 OR 2 288

#493-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on November 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Adair, 1856

Set Post

S. Pine 9" S22 1/4°E, 9 LINKS

Survey, Lapham, 1971, Unrecorded

C-9 to D-9, 2634.7

C-9 to E-9, 5259.5

Survey, Roser, 1994, Unrecorded

Same as LCRC #722-92

C-9 to B-9, 2608.03

C-9 to D-9, 2634.60

CSR, Johnson, 1935

Bk 2. Pg. 70

Two witnesses

C-9 to A-9, 77.50 chains

LCRC, Lapham, 1983

LCRC #441-83

Found sucker rod

Four witnesses

CSR, Johnson, 1935

Bk 2. Pg. 68

C-9 to E-9, 79.90 chains

LCRC, Roser, 1992

LCRC #722-92

Found sucker rod & two 1983 witnesses

Four witnesses and location of roads, E, N, & S

CSR, Lapham, 1960

Bk 3. Pg. 115

Iron, two witnesses

APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman *Paul D. Lapham*

Date 12-13-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found sucker rod and two 1983 witnesses and all 1992 witnesses. Did not find any other witnesses. Verified DNR distances to B-9 and D-9. Accepted sucker rod as best available evidence of the position of the corner. Corner is 3' East of centerline road South and 4' South of centerline road East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458.

Witnesses:

N60°W, 49.60' - Fd spike in 15" R. Pine (OBT)

N15°E, 28.43' - Fd spike in 12" R. Pine (OBT)

N60°E, 51.95' - Fd spike in 10" R. Pine (OBT)

S50°W, 55.21' - Fd spike in 12" Twin R. Pine (OBT)

Signed by

Mark R. Robison

Surveyor's Michigan License No. 27458



Date

12/14/2000