

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE  
(County)

Located in:

Corner Code #

1. Public Land Survey

T20N R 5W

C-13

T19N R 5W

C-1

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson  
Set Post Cor Sec.'s 31 & 32  
Wit. P. Pine 15" N17E 08  
P. Pine 7" N68W 05

road is 40' +/- E. Set D.N.R. Mon and  
Ced. Post. Fd 1/2" rerod w/RLS cap  
"J.S.#18664" N78-51E 62.74'  
Wit.-20" B. Oak North 16.7 (OBT)  
3" Tw. B. Oak S75E 5.1  
7" B. Oak S30W 25.0"  
2" W. Pine S70W 44.5'

8-10-92 Roser LCRC#702  
Restored SW Cor of Sec 32 from (4)  
M. Schaaf (RLS & Dept Forestry Chief)  
1941 NBT's; (3 stp. remains and one  
live B. Oak) Schaaf notes indicate he  
had orig evidence here. Ctr. N-S sand

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found D.N.R. Monument and witnesses. Found remains of GLO 15"  
Pine.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted D.N.R. Monument as Clare County Remonumentation Monument. Accepted as perpetuation of original corner.

Witnesses:

North 16.70', N&T, 22" B. Oak (OBT)  
S75E 5.10', N&T, 5" Twin B. Oak (OBT)  
S30W 25.00', N&T, 8" B. Oak (OBT)  
S70W 44.50', N&T, 3" W. Pine

Signed by Mark R. Robison

Date 10-01-97

Surveyor's Michigan License No. 27458

RECEIVED  
#207-97  
97 OCT 15 AM 10:50

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY  
SUMMERFIELD  
GREENWOOD

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Taylor  
Date 9-23-97

