

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>D-5</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

199900007868
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 32 - 32

Instrument Liber Page
199900007868 OR 2 32

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
Set 1/4 Sec. Post
S. Pine 9 - N52W 71
S. Pine 7 - S62 1/2 E 160

1914 Johnson, CSR 6-117
Oak 6 N57E 82
Oak 6 N58W 44

1994 Roser, DNR Plan No. R-18-AB
Meas. N89-43-54W, 2635.77
Meas. S89-43-54E, 2635.77

1992 Roser, LCRC #689
Re-established S1/4 Cor midway on
line between fd Sec. Cors 1/2 Mi. E&W.
E-W Sand Road is 85' +- South
N65W 13.6 8" R. Pine
N65E 17.6 11" R. Pine
S10E 24.8 5" R. Pine
S55W 14.9 10" R. Pine

APPROVED LAND CORNER
P.A. 345 of 1980
Clare County

Chairman Paul J. Tappin
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.
Fd D.N.R Monument with cedar post 1 1/2 feet East. All DNR witnesses were to face of R. Pines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted 4" capped DNR Monument as Clare County Remon Corner. Position is accepted method of re-establishment of the corner.
Witnesses:

N65W 13.94 Set N & T in 12" R. Pine (OBT)
N65E 18.06 Set N & T in 14" R. Pine (OBT)
S10E 25.00 Set N & T in 8" x 4" Tw. R. Pine (OBT)
S55W 15.07 Set N & T in 12" R. Pine (OBT)



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 9-15-99