

**SURVEY &
REMONUMENTATION**

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 20N R. 5W D-9
T. _____ R. _____
T. _____ R. _____
2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

200000010162
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-15-2000 At 07:44 am.
LAND CORNER 9.00
OR Liber 2 Page 285 - 285

Instrument Liber Page
200000010162 OR 2 285

#490-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on November 28, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Adair, 1856
Set Post
S. Pine 6" N30°E, 94 LINKS
Y. Pine 10" S40°W, 59 LINKS

LCRC, Lapham, 1983 LCRC #441-83
Found pinch pipe
Four witnesses

CSR, Johnson, 1935
CSR, Bk 2. Pg. 68
Oak 12" N58°E, 33 LINKS
C-9 to E-9, 79.90 chains

LCRC, Lapham, 1992 LCRC #675-92
Found pinch pipe
Four witnesses

Survey, Lapham, 1971 Unrecorded Survey
D-9 to C-9, 2634.7 feet
D-9 to E-9, 2624.8 feet

Survey, Roser, 1994
Fd 1/2" pipe, added 5/8" x 34" rerod w/P.S. cap
D-9 to C-9, 2634.60 feet
D-9 to E-9, 2624.56 feet

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul S. Lipp*
Date 12-13-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found 5/8" x 36" rerod with pipe next to it. Verified one 1992 witness. Replaced P.S. cap on rerod with Clare County Remon Cap. Remove pipe. Verified 1971 and 1994 distance from D-9 to C-9 and E-9. Accepted 5/8" rerod as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Clare County Remon Cap marked P.S. #27458 on existing 5/8" rerod.

Witnesses:
N20°W, 29.15' - Fd spike in 16" R. Pine
N26°E, 33.26' - Fd spike in 16" x 18" R. Oak (OBT)
S09°W, 32.15' - N & T in 32" R. Oak
S55°E, 76.28' - N & T in 8" J. Pine



Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 12/14/2000