

SURVEY &
REMONUMENTATION

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>20N</u> R. <u>5W</u> | <u>E-5</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

199900007867
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 31 - 31

Instrument Liber Page
199900007867 OR 2 31

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Adair
Set Post Cor Sec. 8-9-16-17
S. Pine 9 S56W 43 links
S. Pine 10 N32E 96 links
- 1914 Johnson, CSR 2-50 & 6-117
Oak 6" N69E 56
Oak 10" S45-30W 99
Meas. West 80.09 1/2
- 1914 Johnson, 6-118
S. Pine 8N22 1/2 E77
S. Pine 8" N45 1/2 W83
Meas. East 80.04 1/2
- 1976 Gourdie-Fraser, (132) 2-238
Fd DNR cap & Iron
N40W 58.08 8" Oak
S50W 41.30 5" N. Pine
N80E 28.22 6" N. Pine
Meas. East 2635.4

- 1982 Wilcox, LCRC 422
Fd. DNR Cap 100' W of
centerline Jackson Rd
N69E 7.13, 8" J. Pine
N83E 28.26, 6" R. Pine
S49W 41.28, 6" R. Pine
N35W 58.05, 6" Oak
- 1979 McClung, LCRC #451
Fd. DNR Cap
S.W. 41.2 8" N. Pine
N45W 58.10 8" W. Oak
N85E 28.30 8" N. Pine

- 1989 Roser, LCRC 728
Fd. Cons. Dept. Mon for N.W. corn Sec. 16
In 1962 Ostling fd good stake bottom
and remains of Arthur Johnson's 1914 OBT'S.
N78 E 28.22 10" R. Pine
S42W 41.27 10" R. Pine
N40W 58.05 9" Oak
S68W 56.1 14" R. Pine

- 1994 Roser, DNR Plan No. R-18-AB
Meas. N 89-43-54W, 2635.77
Meas. S 89-54-54E, 2636.15

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.
Fd 1976, 1979, 1982 and 1989 witnesses. Fd DNR Monument with ced. post 1 ft N.W.

Chairman David S. Leph
Date 9-15-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted 4" capped D.N.R. Monument as Clare County Remon corner. Accepted as perpetuation of C.S.R. corners
Witnesses:

- N84°E 28.25 Spike in 15" R. Pine
S42°W 41.29 Spike in 12" R. Pine
S68°W 56.60 Spike in 16" R. Pine (DNR used face) (OBT)
N30°W 58.05 Spike in 10" Oak (OBT)

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



9-15-99