

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

Table with columns: (County), Located In:, Corner Code#:
1. Public Land Survey T. 20N R. 5W F-7
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

199900007875
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 39 - 39

Instrument Liber Page
199900007875 OR 2 39

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13 containing numbers 6-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Adair Set 1/4 Sec. Post S. Pine 8" S75W 119 S. Pine 9" N07E 179
6-89 McClung, (132) 3-242 Found N1/4 Corner Set iron 33' South
Circa 1900, CSR BK6-139 Cedar Post 12 S8° 30' E 52
9-89 Lapham, Unrec Survey Fd 3/4" Pipe Witnesses same as (132) 2-238
12-76 Gordie-Fraser, (132) 2-238 Fd 3/4" Pipe S20W 31.13 P.P. South 38.83 Cemetery Fence Meas. West 2648.31 to E-7 Meas. East 2647.94 to G-7
8-92 Roser LCRC #737 & DNR Plan R-18-AB Fd 1/2" Pipe - Replaced w/ 5/8" x 34" rerod N.W. Cor of cemetery Fn is South 38.6' N36°W 52.92 16" R. Pine N04°W 43.28 28" Tw. Oak S10°W 31.10 P.P.
12-76 DeLaMater, (132) 2-233 S00° 25' W, 33.00. Fd IR w/LS cap 13037 References S1/4 Cor Sec. 16 Set Ced Post North 33', Meas. East 2648.09 and Meas. West 2648.34
No Witnesses

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman [Signature]
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.
Found 5/8" rerod and witnesses. Cemetery fence has been extended to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Clare County Remon Cap marked P.S. #27458 on existing 5/8" rerod. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
N78°E 67.50 N & T in 20" R. Pine
S36°E 47.69 N & T in 4" Fir
S08°W 31.10 N & T in P.P. (OBT)
N32°W 52.98 Spike in 18" R. Pine (OBT)

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 9-15-99