

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

Form with fields for 'Corners in Clare', 'Public Land Survey', 'Public Controlling in Section', 'Miscellaneous Property in Section', 'Lot No.', and 'Private Claims'. Includes 'Located In' and 'Corner Code#' fields.

199900007865
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 29 - 29

Instrument 199900007865 OR Liber 2 Page 29

Register of Deeds Stamp & File Number

Mark R. Robison, in a field survey on July 19, 1999, do hereby certify that under requirements of A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

856 Adair
Set Post Cor Sec 9-10-15-16
Pine 11 N12E 38
Pine 22 S67 1/2W 188

914 Johnson, CSR 6-118
Pine 22 S67 1/2W 188 (Gov't)
Meas. West 80.04 1/2

976 Gourdie-Fraser, (132) 2-238
1/2" 2" Pipe
West 47.04 P.P.
North 11.5 8" N. Pine
15E 21.0 6" N. Pine

1989 Roser, LCRC #728
Fd 1 1/2" Pipe - Probably set by Schaff
His 1942 records say he fd. stump of
S.W GLO BT in place. Used by
Gourdie-Fraser.
N05°W 11.50 12" R. Pine
S70E 15.52 8" R. Pine
S15E 21.00 11" R. Pine
S87W 47.04 P.P.

1994 Roser, DNR Plan No. R-18-AB
Meas. N89-56-14W, 2636.01
S89-43-40E, 2607.39

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman [Signature]
Date 9-15-99

2. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.
Fd 1 1/2" pipe 1 foot above ground with D.N.R Post 1' N.W. Fd all 1976 and 1989 witnesses.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare Co. Remon cap marked P.S. #27458 in 1 1/2" pipe. Accepted as best available evidence of perpetuation of C.L.O. corner.
Witnesses:
N05W 11.50 Spike in 12" R. Pine (OBT)
S60E 15.52 Set N & T in 8" R. Pine (OBT)
S15E 21.00 Set N & T in 11" R. Pine (OBT)
S87W 47.04 Set N & T in P.P. (OBT)



Signed by Mark R. Robison

Date 9-15-99

Surveyor's Michigan License No. 27458