

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>G-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007876
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 40 - 40

Instrument 199900007876 OR
Liber 2 Page 40

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
Set Post Cor Sec. 15, 16, 21, 22
Y. Pine 18, N56W 759 Lks.
Y. Pine 10, S35E 269 Lks.

Circa 1900
Oak 20 S48-15E 78
Oak 18 N68E 121 3/4
G-7 to E-7 79.70

12-76 Gordie-Fraser, (132) 2-238
Fd 1" Pipe
N5E 39.77 Tree
S20E 64.14 9" N. Pine
Meas. West 2647.94 to F-7
Meas. East 2644.28 to H-7

8-92 Roser LCRC # 725 & DNR Plan R-18-AB
Accepted fd 1" pipe (G.F.) w/RLS cap for
SE Cor Sec. 16. Cor is ctr E-W
gravel road. Trail South is 54' West.
Fd old shotgun barrel S05°46 E
28.0 feet. Fd 1" pipe witnessed
and used by Gourdie-Fraser, Inc.
N60°W 91.40 7" R.Pine
N05°E 39.78 17" Oak
S10°E 64.05 13" R. Pine
S25°W 67.05 16" R. Pine
Ced Post due N. 33'
Meas. East 2644.37
Meas. West 2648.08

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul B. Lapp
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.

Found iron in C.L. grave road and 1992 witnesses. Searched for CSR witnesses but could find no evidence. Could not determine origin of shotgun barrel. Accepted DNR corner but did not remove gun barrel.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 36" rerod with Clare Co. Remon cap marked P.S. #27458 in C.L. Gravel Road. Accepted as best available evidence of accepted position of corner.

Witnesses:
N05°E 38.78 Spike in 20" Oak (OBT)
S10°E 64.16 Spike in 15" R. Pine (OBT)
S25°W 67.14 N & T in 18" R.Pine (OBT)
N60°W 91.38 Spike in 10" R. Pine (OBT)
S05° 46'E 28.00 shotgun barrel

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 9-15-99