

**SURVEY &
REMONUMENTATION**

MAR 24 2000

**SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare
(County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>H-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007877
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 41 - 41

Instrument Liber Page
199900007877 OR 2 41

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1856 Adair
Set 1/4 Sec. Post
S. Pine 12 S71W 490 Lks.
S. Pine 10 N40E 404 Lks.

**APPROVED LAND CORNER
P.A. 345 of 1990
Clare County**
Chairman David A. Papp
Date 9-15-99

12-76 Gordie-Fraser, (132) 2-238
References Corner - No Witnesses
Meas. West 2644.28 to G-7
Meas. East 2644.28 to I-7

1-85 Wilcox LCRC #482
Set iron & cap from three remaining witnesses from Schaaf survey of record on July 26, 1941. Corner falls 33 feet south of C.L. E-W gravel road.
S29E 20.46 18"x 10" Twin Red Oak
S15W 69.30 12" Red Oak Stump
N35W 110.88 18" Red Oak
N19E 83.35 10" Red Oak
N85W 3.38 6" J. Pine

8-92 Roser LCRC #725 & DNR Plan R-18-AB
Re-established 1/4 Cor to Sec 15 & 22 midway and on line between Sec Cors. This fits Gordie-Fraser Sec. 15 Section Subdivision in 1976.
N35W 99.45 22" B. Oak
N20E 74.25 13" R. Pine
S25E 32.33 21" B. Oak
S10W 84.74 17" B. Oak
Meas. East & West 2644.37 on line

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.

Corner falls 23 feet south of C.L. gravel road. Fd. DNR Mon. and post and witnesses. Did not find Wilcox corner or witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted DNR monument as Clare Co. Remon Corner. Accepted as best available evidence of accepted method of reestablishment of corne:
Witnesses:

S32°E 32.33 Spike in 24" x 12" Twin Oak (OBT)
South 84.71 Spike in 20" Oak (OBT)
N20°E 54.85 Spike in 8" J. Pine
N30°W 99.48 Spike in 28" Oak (OBT)

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 9-15-99