

**SURVEY &
REMONUMENTATION**

MAR 24 2000

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in <u>Clare</u> (County)		
	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>J-5</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007862
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 26 - 26

Instrument Liber Page
199900007862 OR 2 26

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair Set 1/4 Sec Post S. Pine 8 S27E 407 No other trees near	1990 Roser Accept 3/4" Pinch Pipe for 1/4 Cor. Ctr of E-W winding trail is South 27" Fd 3 PBL witnesses. Added DNR Mon N25W 8.52 10" J. Pine S05E 44.00 6" R. Pine S20W 58.5 7" R. Pine S50W 66.8 8" R. Pine
---	---

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman *[Signature]*
Date 9-15-99

1994 Roser, DNR Plan No. R-18-AB
Meas. N89-58-24W 2650.52
Meas. S89-45-03E 2648.64

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
See dossier for detailed report.

Fd DNR Monument with 18" high x 8" dia cedar post 2 feet N.W. Fd DNR witnesses and one 1971 witness. Meas. 54 feet N.W. to C.L. of N.E./S.W. Trail. Meas. S. 27 feet to C.L. of E-W Trail. DNR used face of R. Pines as witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted 4" capped D.N.R Monument as Clare County Remon Corner. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
N10°W 8.52 Spike in 10" J. Pine (OBT)
S05°E 44.78 Set N & T in 10" R. Pine (OBT)
S20°W 58.68 Set N & T in 10" R. Pine (OBT)
S50°W 67.07 Set N & T in 10" R. Pine (OBT)
S65°W 98.82 Set N & T in 12" R. Pine
West 43.09 Spike in 16" J. Pine (OBT)



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 9-15-99