

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>K-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007880
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 09-20-1999 At 11:15 am.
 LAND CORNER 9.00
 OR Liber 2 Page 44 - 44

Instrument Liber Page
 199900007880 OR 2 44

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
 Set Post Cor Secs. 13, 14, 23 & 24
 Oak 12 N62E 62 Lks.
 W. Pine 34 S64W 37 Lks.

4-70 Meyers, Unrec Survey
 References Corner - No Witnesses
 Meas. West 1324.65 to 1/8 line
 Meas. South 2621.68 to K-8

10-71 Lapham, LCRC #12
 Fd 1/2" bar from prev survey
 N40W 26.03 3" Oak
 S45E 30.77 8" Wild Cherry

8-92 Roser, LCRC #729 & DNR Plan R-18-AB
 Accepted Fd sucker rod for S.W. cor S-13.
 R.L.S. Lapham rec. this corner in 1971.
 Fd old R/W Fn. remains E'ly 28 feet
 Ctr. E-W Trail is 6' +- S.
 N30°W 26.03 6" Tw. W. Oak
 N15°W 39.09 7" W. Pine
 N55°E 42.02 2" Maple
 S55°E 38.15 8" Oak
 Meas. West 2647.99

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman *David D. Lapp*
 Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.
 Fd 5/8" x 18" sucker rod, two 1971 witnesses and four 1992 witnesses. Meas. West 2647.99 to J-7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
 N22°W 25.95 Spike in 8" x 6" Tw. Oak (OBT)
 N12°W 39.05 Spike in 8" W. Pine (OBT)
 N61°E 42.06 Spike in 3" Maple (OBT)
 S54°E 38.12 Spike in 10" Oak (OBT)



Signed by *Mark R. Robison*
 Surveyor's Michigan License No. 27458

Date 9-15-99