

**SURVEY & REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>K-9</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims _____		

200000010161  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 12-15-2000 At 07:44 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 284 - 284

Instrument Liber Page  
 200000010161 OR 2 284

#489-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on November 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Adair, 1856  
 Set Post  
 Y. Pine 22" N52°W, 29 LINKS  
 Y. Pine 24" S60°E, 48 1/2 LINKS

LCRC, Roser, 1992  
 LCRC #717-92  
 Fd 1/2" rod in Mon. Box at int. Black-top road N-S and gravel road East.  
 Four witnesses and cedar post.

CSR, Johnson, 1935  
 Bk 2, Pg. 64 & 65  
 No Witnesses  
 K-9 to I-9, 79.80 chains  
 K-9 to M-9, 81.67 chains

Survey, Roser, 1994, Unrecorded  
 Same as LCRC #717-92  
 K-9 to I-9, 5264.58  
 K-9 to M-9, 5396.88  
 K-9 to L-9, 2684.49

LCRC, Lapham, 1977  
 LCRC #314-77  
 Fd 1" pipe at int. Rds. N-S-E  
 Three witnesses

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul S. Leph  
 Date 12-13-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found 1/2" rod in Mon. Box in asphalt pvm't. Verified two 1977 witnesses (stumps) and three 1992 witnesses (one was stump). Verified DNR distances to I-9, L-9, and M-9 by G.P.S. Accepted 1/2" rod as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Remon Cap marked P.S #27458 in Mon. Box.  
 Witnesses:  
 N49°E, 89.00' - N & T in 10" Oak  
 S40°E, 79.05' - N & T in 10" J. Pine  
 N38°E, 90.95' - N & T in 10" x 12" Twin R. Oak  
 S85°W, 50.83' - N & T in 3" W. Pine

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458



Date 12/14/2000