

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>L-5</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

199900007860
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 24 - 24

Instrument 199900007860 OR Liber 2 Page 24

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on August 25, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
Set 1/4 Sec. Post
Spruce Pine 9 N87 1/2 E 26
Spruce Pine 6 S31 1/2 W 174

1930 Johnson, CSR 6-121
Gov't Cor. Fd.

1991 Roser
Fd 1 1/2" Pipe set in 1940 by M. Schaaf from USBT in place. K. Ostling fd & rec. cor in 1962. (Stub now on ground but scribe marks visible). Fd remains of 4 M. Schaaf witnesses & 2 K. Ostling wit stps that fit pipe.
N40W 18.9 7" J. Pine
N38W 83.6 15" J. Pine
N8W 9.3 6" J. Pine
S25E 19.6 2" J. Pine
S45W 15.5 3" J. Pine

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul S. Lepp
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Fd DNR Mon w/ post 2' W. Fd 1 live B.T. and 3 dead B.T.'s. Fd. U.S.B.T stub on ground badly deteriorated. Meas. Approx 2658' West to K-5. Meas. Approx 2628 East to M-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted DNR Mon for Clare Co. Remon Monument. Accepted as best available evidence of the perpetuation of the original corner.

Witnesses:

N12°W 9.51 Fd N & T in 10" J. Pine (OBT)
N50°E 37.54 Set N & T in 16" J. Pine (OBT)
S24°E 47.20 Set N & T in 6" J. Pine (OBT)
N80°W 11.25 C.L. 1 1/2" J. Pine



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 9-15-99