

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 5W L-9
 T. _____ R. _____
 T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000010158
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 12-15-2000 At 07:44 am.
 LAND CORNER 9.00
 OR Liber 2 Page 281 - 281

Instrument Liber Page
 200000010158 OR 2 281

486-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on November 28, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Adair, 1856
 Set Post and two witnesses

Subd, Moore, 1955
 First Addition to Buck Trails, L4. Pg. 16

Survey, Roser, 1994
 Unrecorded DNR Survey
 Same as LCRC #656-92
 L-9 to K-9, 2684.49
 L-9 to M-9, 2712.39
 L-9 to L-10, 2669.31

CSR, Johnson, 1935
 CSR, Bk 2. Pg. 64, one witness
 K-9 to M-9 81.67 chains

Survey, Lapham, 1984, Unrecorded Survey
 Found Sucker Rod.
 Monument 33.0' South & L-9 to L-10, 2670.46

Subd, Johnson, 1952
 Buck Trails Subdivision, L3. Pg. 24
 Monument 33.0 feet South of corner.

LCRC, Roser, 1992, LCRC #656-92
 Fd sucker rod & boat spike
 corner fits one Moore witness & conc. mon to South.
 Set four witnesses & cedar post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found sucker rod and boat spike. Verified one 1935 witness and all 1992 witnesses. Verified distances from L-9 to K-9 and L-9 to M-9 with G.P.S. Accepted sucker rod as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458.

- Witnesses:
- N40°W, 36.8' - N & T in 10" Maple (OBT)
 - S10°E, 71.48' - N & T in 18" R. Pine (OBT)
 - South, 33.00' - Conc. Monument (OBT)
 - S40°W, 51.91' - N & T in 12" R. Pine (OBT)
 - S76°W, 55.44' - N & T in 36" B. Oak (1935 OBT)

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman *Paul H. Lapham*
 Date 12-13-00

Signed by *Mark R. Robison*
 Surveyor's Michigan License No. 27458



Date 12/14/2000