

SURVEY &  
REMONUMENTATION

MAR 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Clare County Remonumentation

SECTION

For Corners in  
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>M-5</u>
	T. <u>20N</u> R. <u>4W</u>	<u>A-5</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007859  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 09-20-1999 At 11:15 am.  
LAND CORNER 9.00  
OR Liber 2 Page 23 - 23

Instrument Liber Page  
199900007859 OR 2 23

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on August 25, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single common corner to  
T20N, R5W, M-5 and T20N, R4W, A-5

A. Description of original monument and accessories and/or subsequent restoration:

1-76 Ostling LCRC #241  
Fd 1/2" iron bar, origin unknown, that seems to fit occupation in Sec 7.  
Probably established in connection with gravel pit but can find no record of same. Set DNR monument & red-top post.  
S80W 21.6 5" J. Pine  
S43E 10.1 6" J. Pine

1838 Nicholson, Set Post Cor. Sec. 12 & 13  
Pitch Pine 10, N13W 17  
Pitch Pine 9, N60W 12

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Leph  
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Found DNR Monument and witness post. Found one 1976 witness. Meas. approximately 2628' West to L-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted DNR Monument for Clare County Remon monument. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

N74°W 14.81 Set N & T in 10" J. Pine  
S50°E 10.35 Set N & T in 12" J. Pine (OBT)  
N18°W 23.82 Set N & T in 8" J. Pine  
N70°E 21.91 Set N & T in 8" J. Pine



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 9-15-99