

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 20 N.R. 5 W.


Clare COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 8 - 9 - 16 - 17

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 28, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" J. Pine N 7 E 34.1'

7" B. Oak S 69 E 34.4'

AND

4" R. Pine S 68 W 56.3'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 16. Found good stake bottom at corner, which we conclude was established by County Surveyor Johnson about 1914. Found corner from remains of his NBTs. Corner falls within one foot of proportionate measure for latitude, and checks other physical features acceptably. Since this corner was established and recorded at a time when evidence of the U. S. survey may have been available, we conclude this to be the best evidence of the proper position for the corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Wetling DATE October 9, 1962
REGISTERED LAND SURVEYOR