

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
CLARE  
 (County)

Located In: \_\_\_\_\_ Corner Code #

- |                                       |                            |                 |
|---------------------------------------|----------------------------|-----------------|
| 1. Public Land Survey                 | T <u>20N</u> R <u>5W</u>   | <u>A-2, B-3</u> |
|                                       | T _____ R _____            | _____           |
|                                       | T _____ R _____            | _____           |
|                                       | T _____ R _____            | _____           |
| 2. Property Controlling in Section    | S <u>6</u> T _____ R _____ | <u>10</u>       |
|                                       | S _____ T _____ R _____    | _____           |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____    | _____           |
|                                       | S _____ T _____ R _____    | _____           |
| 4. Lot No. _____, Recorded Plat _____ |                            |                 |
| 5. Private Claims _____               |                            |                 |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL F. ROSER, in a field survey on JULY 27, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-2	A-2	B-3	10
	THE INTERSEC OF SAND RDS N-S-E-W BEING 13'± N & 12'± N. BETW 1983 & 1990 THE IR BY RLS #18664 WAS DESTROYED. (APPARENTLY BY PIPELINE CONST.) THE IR WAS RESTORED ON 7/27/90 BY ROSER'S SUR CREW. PER RLS #18664 WITS & (CONTINUED BELOW)		

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-2	A-2	B-3	10
DEPT LAND SURVEYOR, K DSTLING RECOV'D A 1/2" IR; BY RLS #18664 JOHN SEDGMAN, (WORKED FOR PAUL LAPHAM ASSOC FOR SOME TIME -SEE KJD FIELD NOTES PG 23, DATED 3-23-76), FOR THE E 1/4 COR OF S-1, T20N-R6W. IN 1983 ROSER'S SUR CREW RECOV'D SAME IR, BY RLS #18664, DURING AN ON-GOING INTERMITTENT, RETRACEMENT SUR IN T20 & 21N-R5W; (CONT. IN 'A')	(CONTINUED FROM 'A' ABOVE.) RECORD PER 1983 (ROSER CREW) TRAVERSE; THE INTERSEC OF SAND RDS N-S-E-W BEING 12'± N & 12'± W. NOTE: THE ABOVE MENTIONED ROADS WERE APPARENT ON THE GROUND BUT ARE NOT NECESSARILY ON THE COUNTY OR PUBLIC ROAD SYSTEM.	FD M. SCHAAF 2" PIPE FOR S 1/4 COR SEC 6. FD 3 M. SCHAAF WITS THAT FIT GOOD AND 2 PINE STPS THAT FIT GLO WITS DATA REAL GOOD.	ESTABLISHED SW COR OF FRL N 1/2 OF FRL SW 1/4 OF SEC 6 PER STANDARD BLM INSTRUCTIONS. CTR OF N-S GRAVEL RD IS 3' N. CTR OF TRAIL E'LY IS 110'± 2' N. CTR OF SAND TRAIL W'LY IS 104'± 4' N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-2	A-2	B-3	10
SET 1" X 35" GALV PIPE W/X-ARM ON BOTTOM & SET PLASTIC RLS CAP IN TOP OF 1" PIPE. 9" R. PINE N55°W 61.96' #7" B. OAK N20°E 39.00' 7" R. PINE S50°E 27.71' #8" R. PINE S75°W 47.97' SET CED POST W/ LOC TAG. EAST 16.5' #RLS #18664 (LAPHAM ASSOC)		DROVE 1" X 6" GALV PIPE W/ALUM DNR CAP IN FD RUSTY 2" PIPE & SET CED POST. 10" MAPLE N25°W 6.9' 10" R. OAK S70°E 20.32' 7" MAPLE S35°E 10.0' 14" OAK S10°W 24.51' #24" Y PINE STP N45°W 39.6' #26" Y PINE STP N68°E 41.6' #MARCUS SCHAFF WITS.	DROVE 3/8" X 34" REROD W/RLS CAP. 15" R. PINE N30°W 72.0' 8" R. PINE N25°E 51.3' CTR GAS WELL #942 S80°W 71.8' SET CED POST W/ LOC TAG. EAST 16.5'

Signed by Carl F. Roser 5-22-92 Date \_\_\_\_\_  
 Surveyor's Michigan License No. 12028

