

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| | | | | |
|--------------------------------------|---|----------------------|--|-----------|
| For Corners In: | | | | |
| Clare | Located In | Corner Code # | | |
| (County) | | | | |
| 1. Public Land Survey | T _____ R _____ | | | |
| | T _____ R _____ | | | |
| 2. Property Controlling In Section | S <u>3</u> T <u>20N</u> R <u>5W</u> _____ | | | <u>8</u> |
| | S <u>3</u> T <u>20N</u> R <u>5W</u> _____ | | | <u>11</u> |
| 3. Miscellaneous Property In Section | S _____ T _____ R _____ | | | |
| | S _____ T _____ R _____ | | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug., 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | 3 | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

8 - None



11 - Paul Lapham & Assoc. - 1995
Order No. C-946169
Set 1/2" x 18" Capped Rebar - M. Robison

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

8 - CW 1/16 Cor., Sec. 3, T20N,R5W. Set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM procedure.

11 - SW 1/16 Cor., Sec. 3, T20N,R5W. FND. 1/2" x 18" long Capped Rebar, PS # 9433. Replaced Iron w/ 2", Alum. Cap on 5/8" x 34" Rebar. Monument accepted as the Best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 - 2" Alum. Cap on 5/8" x 34" Rebar
S64°W 8.21' to N&T in S. Side 14" W. Oak
S24°E 45.77' to N&T in W. Side 11" R. Pine
N8°E 24.72' to N&T in E. Side 5" Scotch Pine
N73°E 44.93' to N&T in S. Side 12" R. Pine
Set blue Carsonite post 1' SE.

11 - 2" Alum. Cap on 5/8" x 34" Rebar
N33°W 25.83' to N&T in NE. Side 7" R. Pine
N54°W 31.67' to N&T in NW. Side 14" R. Pine
S17°E 24.83' to N&T in W. Side 7" R. Oak
S31°W 39.52' to N&T in NW. Side 11" Tw. R. Oak
Set blue Carsonite post 1' E.

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/5/1999

2286