

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Clare</u> (County)	Located In _____	Corner Code # _____
1. Public Land Survey	T <u>20N</u> R <u>5W</u>	<u>D12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Nov. 02, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
D12 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D12 - C 1/4, Sec. 32 - No evidence found of existing corner. Set stamped 2" Alum. Cap on 5/8" x 34" rebar at intersection of 1/4 lines per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D12 - 2" Alum. Cap stamped on 5/8" x 34" rebar
 N03°E 15.07' to set N & T in W. side 18" R. Pine
 N82°E 16.42' to set N & T in N. side 7" Oak
 S34°E 20.99' to set N & T in NE side 9" Twin R. Maple
 S86°W 23.59' to set N & T in S. side 17" R. Pine
 Set Blue Carsonite Post 1' NW



Signed by: Craig W. McVean Date: 1/31/2005
 Surveyor's Michigan License No.: 39088