

CLARE County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 E V  
 # 284-98  
 98 NOV 18 AM 9:56  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. McAULAY

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R06W T19N R06W T R T R	<u>A-13</u> A-1
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R6W A-13 and T19N R06W A-1

A. Description of original monument and accessories and/or subsequent restoration:  
 A-13: 1837 Hodgson  
 Set post cor T19 & 20N, R6 & 7W  
 Wit-Hemlock 16 S35W 17  
 Beech 14 N17W 55  
 1856 Coleman  
 At 76.60 int N-S line 417 North of Post  
 7-19-41 CSR 2-124  
 Iron stake  
 Wit-Poplar 24" NE 43'  
 Fen Post NW 42'  
 7-16-79 Wilcox LCRC#367  
 Fd 1/2" rerod in 2" Tile  
 Wit-N05W 25.05 P.P.  
 N45W 36.03 Tele Riser  
 N60W 46.10 E. End Culvert  
 N25E 91.95 SW Cor Hse  
 01-27-86 Roser LCRC#535  
 Fd & accepted 1/2" rerod in 3" tile (buried 3") for NW Cor Sec 6 (19-6) E-Wdirt rd in curve is South 11'+/- Cor is in line with old fences to N & S.  
 Wit-North 25.00 P.P.  
 N30E 91.9 SW Cor Brick Hse  
 N60W 46.0 E. End Steel D'wy Culv  
 South 33' Set Ced Post w/Loc Tag

**SURVEY & REMONUMENTATION**  
 NOV 25 1998  
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 A-13: Found 1/2" rerod in 3" clay tile and all 1979 and 1986 witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-13: A-13: Set 5/8" x 36" rerod with Clare County Remonumentation Cap marked P.S.#27458 in clay tile. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 N05W 25.05', nail & tag, P.P. (OBT)  
 N45W 36.03' Center of Telephone Riser (OBT)  
 N60W 46.00 East End of 10" CMP (OBT)  
 N25E 91.95' SW Corner Brick House (OBT)  
 South 33.00', nail & tag, Cedar Post (OBT)



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman [Signature]  
 Date 9-8-98

Signed by [Signature]  
 Surveyor's Michigan License No. 27458

Date 11-16-98