

SURVEY & MONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T. <u>20N</u> R. <u>6W</u> | <u>E-12</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

200000010168
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 12-15-2000 At 07:44 am.
 LAND CORNER 9.00
 OR Liber 2 Page 291 - 291

Instrument Liber Page
 200000010168 OR 2 291

#496-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 12, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Coleman, 1856
 Hemlock 8" N37°E, 43 LINKS
 Hemlock 8" S51°W, 26 LINKS

Survey, Lapham 1972, not recorded
 Same as LCRC #65-72
 E-12 to F-12 = 2604.11
 E-12 to G-12 = 5213.87
 E-12 to E-13 = 2638.21
 E-12 to E-11 = 2617.77

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman *Paul B. Leph*

Date 12-13-00

CSR - Harper, 1901
 Long triangular shaped stone,
 crockery and tin can
 E-12 to D-12 = 39.35 chains (2597.1')

Survey, Lapham 1986, Not recorded
 Same as LCRC #65-72
 E-12 to E-13 = 2638.34
 E-12 to D-12 = 2633.38

Lapham 1972, LCRC #65-72
 Set 1/2" bar, 3 witnesses
 (Field notes show set in centerline intersection)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO or CSR evidence found. Found 1/2" x 18" iron in Mon. Box at intersection of centerlines. Excavated to 3' and found nothing else. No evidence of other corner positions. Verified 1 witness from LCRC #65-72. Measured distances; E-12 to G-12 = 5213.88; E-12 to E-11 = 2617.64; E-12 to E-13 = 2638.21. Accepted found iron as best available evidence of corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 26" rered with Clare County Remon cap marked P.S #27458 in Mon. Box

Witnesses:
 N24°W, 82.94' - N & T in 12" x 12" R. Oak
 N55°E, 48.78' - Fd N & T in P. Pole (stub) (OBT)
 S29°W, 82.12' - N & T in 13" Ash
 S66°E, 115.80' - N & T in 13" J. Pine
 N18°E, 134.04' - N & T in 18" R. Pine



Signed by *Mark R. Robison*
 Surveyor's Michigan License No. 27458

Date 12/14/2000