

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 E 10 A D  
 # 57-94  
 94 NOV 28 AM 10:37  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>6W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |   |  |
|---|--|
| 1856 COLEMAN, G.L.O. PG.530<br>POST<br>WIT.-(1)HEMLOCK 10" N18°E 35 LKS.<br>(2)B. ASH 12" S27°W 11 LKS. | 12-10-82 CAVANAGH, L.C.R.C. #427<br>FOUND 1/2" RE-ROD IN LINE WITH FENCE<br>WIT.-(5)S21°W 21.2' 6" ELM<br>(6)SOUTH 33.0' CONCRETE PLAT MON.<br>(7)N0°40'W 33.0' 2" PIPE/REMON/CAP<br>(8)N52°E 36.05' 7" POPLAR |
| 9-17-07 C.S.R. L.6-PG.274<br>WIT.-(3)TAMARACK 2" N40°W 35 LKS.  | 1-6-83 CAVANAGH (132) L.2-PG.753<br>1/2" RE-ROD<br>WIT.-(5),(6),(7) & (8) ABOVE<br>(9)FENCE NORTH 31' WEST   |
| 9-21-09 A. JOHNSON, C.S.R. L.4-PG.124<br>WIT.-(3)ABOVE  |  |
| OCT. 28-1960 LAPHAM, PLAT OF WEST CLAM RAPIDS, L.5-PG.6   |  |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x18" RE-ROD IN ASPHALT PAVEMENT. HAD EVIDENCE OF SOME OTHER METAL IN HOLE. EXCAVATED TO 5'. EVIDENCE WAS STILL THERE.  
 FOUND WITNESSES #5,6,7, & 8.

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul B. Sepp  
 Date Nov 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:  
 S21°W 21.1' 14" ELM - NAIL & TAG (5)  
 SOUTH 37.3' METAL FENCE POST (4" I-BEAM)  
 N0°40'W 33.01' 2" PIPE/RE-ROD/CAP (7)  
 N38°E 40.8' 12" POPLAR -NAIL & TAG  
 N52°E 36.05' 7" POPLAR - NAIL & TAG (8)



Signed by Mark R. Robison Date 11-23-94  
 Surveyor's Michigan License No. 27458