

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in

CLARE  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 20N R 6W G-3
- T      R
- T      R
- T      R
- T      R
- 2. Property Controlling in Section S      T      R
- S
- T      R
- 3. Miscellaneous S      T      R
- Property in Sec. S      T      R
- 

#242-97  
97 NOV -4 PM 3:16

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McCAULAY

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4				3		2			1	
3													
4	7	8	9				10		11			12	
5													
6	16	17	16				15		14			13	
7													
8	19	20	21				22		23			24	
9													
10	30	29	28				27		26			25	
11													
12	31	32	33				34		35			36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Coleman 6-23-86 J. Ray (132) 2-942
- Set Post-Cor. Sec.'s 3,4,9 & 10 References Corner in Sec. Subd.
- Wit.-Hem. 12' N37 1/2W 2 l. 10-02-90 McClung (132) 3-244
- Hem. 10' S80E 22 l. Found NW Sec. Cor. 1/2" rerod
- 9-20-74 McClung Wit.-S55E 69.9 Pow. Pole
- L.C.R.C.# 194 & (132) 1-927 S40W 47.25 Pow. Pole
- Fd. 3/8" rod
- Wit.-S50E 69.5 Util. Pole
- N55E 87.2 - 20" W. Ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 9" rerod. Found 1974 and 1990 witnesses. Corner falls in centerlines of road intersection. Excavated but found no other evidence.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul A. Leph  
Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3: Corner common to Sections 3, 4, 9 & 10. Set 5/8" x 36" rerod with 3" Clare County Monument Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- S55E 69.90', nail & tag, P.P. (OBT)
- S40W 47.25', nail & tag, P.P. (OBT)
- N28W 56.16', nail & tag, P.P.
- S69W 78.28', nail & tag, 14" Twin R. Pine

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

