

CLARE COUNTY REMONUMENTATION

NOV 18 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

241-97
97 NOV -4 PM 3:16

REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McAULAY

Register of Deeds Stamp & File Number

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 6W	G-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **MARK R. ROBISON**, in a field survey on **July 1**, 19 **97** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Coleman Wit.-S86E 69.15 Util. Pole
- Set Post Cor. Sec.'s 9, 10, 15 & 16 S78W 38.65 10' Ash
- Wit-Hem 12" N20W 8 L & Beech 6" S61E 19 L. 9-20-74 McClung
- 6-19-06 Johnson C.S.R. 2-61 (132) 1-927 & L.C.R.C.# 194
- Wit.-W. Pine Stump 16" S23E 70 Wit.-same as (132) 1-926
- Aspen 8" N02E 84 6-23-86 J. Ray (132) 2-942
- Undated C.S.R. 6-255 Fd. iron & cap in center road
- Old Cor. - 79.00 East to Sec. Cor. Wit.-S80W 75.35 - 18" Oak
- 6-21-74 McClung N50W 55.60 Cor. Fe. Post
- (132) 1-926 & L.C.R.C.# 193 S80_ 69.20 P.P.
- Fd. Steel fence Post & 3/4" rod 3-30-89 Roser L.C.R.C.# 579

- Fd. Iron for NW Cor, Sec. 15. Cor. is McClung 1974 Corner. Fd. P. Pole wit. & stmp of BT. Cor. is 6" deep in center of N-S Bit. Rd. Ken Ostling here in 1975.
- Fd. R.L.S. cap in threaded end of 3/4" sucker rod.
- Wit.-S65W 79.65 clump of 7 Maples 3"-12"
- West 75.32 19" R. Oak
- N35W 55.57 Fn. Cor. (W & S)
- S85E 69.20 P.P.
- West 33' Set Ced. Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 18" sucker rod over 18" T-bar and 6" square headed spike. Found 1974, 1986 & 1989 witnesses.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul A. Taylor*

Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5: Corner common to Sections 9, 10, 15 & 16. Set 5/8" x 36" rerod with 3" Clare County Monument Cap marked P.S.#27458 in Monument Box. Accepted as best available evidence of accepted position of the corner.

- Witnesses:
- S65W 79.65', nail & tag, clump of 7" - 14" Maples (OBT)
- West 75.32', nail & tag, 22" R. Oak (OBT)
- N35W 54.90', nail & tag, Fence Cor. Post (OBT)
- S85E 69.20', nail & tag, P.P. (OBT)

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 10-31-97

