

NOV 18 1997

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

#244-97

97 NOV -6 PM 3:17

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

For corners in

CLARE

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 20N R 6W G-6
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Coleman 12-08-82 Cavanagh (132) 2-753  
Set gr. Sec. Post References L.C.R.C.# 193  
Wit.-Ham 36" N55E 3 L.  
Sug 20" S67W 27 L.

6-21-74 McClung  
(132) 1-926 & L.C.R.C.# 193  
Set 3/4" rod & cap on-line & equal dist.  
Wit.-N88W 48.0 38" Beech  
N27W 133.0 24" Walnut

3-30-89 Roser L.C.R.C.# 579  
Fd. iron for W 1/4 Cor., Sec. 15, re-est.  
by McClung in 1974. Dept. survey or  
Ken Ostling was here in 1975. Cor. falls  
in Center of Bit. road. Fd. R.L.S. cap on  
threaded end of 3/4" sucker rod.  
Wit.-S45W 44.3 10" Ash  
N85W 47.4 42" Beech  
N20W 132.8 22" Walnut  
West 33' Fn. Cor. (W-S)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 12" sucker rod. Found all 1974 & 1989 witnesses. Excavated but found no further evidence.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Lipp

Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6: 1/4 Corner common to Sections 15 & 16. Set 5/8" x 36" rerod with 3" Clare County Monument Cap marked P.S.#27458 in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
S45W 44.30', nail & tag, 15" Ash (OBT)  
N85W 47.40', nail & tag, 44" Beech (OBT)  
N20W 132.80', nail & tag, 26" Walnut (OBT)  
S64E 34.08', nail & tag, 12" B. Cherry

Signed by Mark R. Robison

Date 10-31-97

Surveyor's Michigan License No. 27458

