

RECEIVED
 E I O A D
 # 60-94
 94 NOV 28 AM 10:37

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE (County)	Located In:	Corner Code ##
1. Public Land Survey	T 20N R 6W	G-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 COLEMAN, G.L.O. PG.529
POST
WIT.-(1)BEECH 18" N56°W 8 LKS.
(2)BEECH 6" S79°E 26 LKS.
 - 9-17-07 C.S.R. L.6-PG.274
WIT.-(3)CORNER TWP. HALL
S43 1/2°W 40 LKS. (SEE BELOW)
(4)TELE. POLE 6" N46°E 60 LKS.
 - 9-21-09 A. JOHNSON, C.S.R. L.4-PG.124
WIT.-(3)COR. TWP. HALL S43 1/2°W, 110 LKS.
(4)AS ABOVE
 - 7-15-72 COURTRIGHT (132) L.1 -PG.186
1" SQUARE IRON BAR
WIT.-(5)S45°E 47.43' COR. FENCE POST
(6)S55°E 66.54' POWER POLE
(7)N30°W 67.39' POWER POLE
 - 9-7-72 COURTRIGHT, (132) L.1-PG.330
1" SQUARE IRON BAR
WIT.-(5), (6) & (7) ABOVE
 - 7-18-72 COURTRIGHT, L.C.R.C. #92
1" SQUARE IRON BAR
WIT.-(5) (6) & (7) ABOVE

- 6-21-74 MCCLUNG L.C.R.C. #193
IRON ROD
WIT.-(8)NE COR. TWP. HALL S32°W 66.30'
(6)UTILITY POLE S52°E 66.90'
- 3-30-89 ROSER L.C.R.C. #578
1 1/4"x2" IRON
WIT.-(3)NE COR. FDN. BEFORE ADDITION
S42°W 71.5'
(6)POWER POLE S60°E 66.45'
(7)SHORT TREATED POST W/TELE
RISER N25°W 67.45'
(8)NE COR. TWP HALL S37°W 66.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"x2"x33" BAR IN ASPHALT PAVEMENT. EXCAVATED 3 1/2 FEET DOWN. FOUND NO OTHER EVIDENCE. FOUND WITNESSES #3, 6, 7 & 8.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Steve B. Laphan
 Date Nov 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:
 S43 1/2°W 71.55' NE COR. OF FOUNDATION OF TWP HALL (3)
 S55°E 66.7' POWER POLE - NAIL & TAG (6)
 N28°W 67.45' STUB OF POWR POLE - NAIL & TAG (7)
 S68°W 110.1' NW COR. OF FOUNDATION OF TWP. HALL



Signed by Mark R. Robison

Date 11-23-94

Surveyor's Michigan License No. 27458