

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ CLARE _____ Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T20N R06W G-13
 T19N R06W G-1
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECEIVED
 # 290-98
 98 NOV 18 AM 9:56
 REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. McAULAY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

This is a single corner common to T20N, R06W
 G-13 and T19N, R06W G-1

- A. Description of original monument and accessories and/or subsequent restoration:
- G-13: 1838 Nicholson Set Post Cor Secs 33 & 34
 Wit-B. Ash 12" N20W 12
 B. Ash 10" N14E 09
 - 1856 Coleman Set Post Cor Sec 33 & 34
 Wits-Tam 8 N42E 15 & Tam 12 N50W 3
 Note: Coleman resurveyed from S 1/4 cor Sec 31 to meander Post on W side River in Sec 34.
 - circa 1900 CSR 6-220 & 6-221
 Wit-Tamarac 16 S33W 41
 - 12-28-72 Lapham LCRC#86 & Sketch; Set 1/2" Bar Wit-East 12.55 8" Pine
 N5W 16.27 8" Pine & S80W 17.10 4" Pine
 - 2-11-92 Wetherill LCRC#658 & Plat of survey(unrecorded)
 Fd 1/2" rebar 2626.87' from N 1/4 Sec 3
 Wit-S76W 17.07 7" Spruce
 N18E 6.37 6" Spruce&N86E 22.58 8" Maple
 S53E 27.17 8" Spruce
 - 9-15-92 Gourdie-Fraser File Drawing
 Fd 1/2" Iron bar 40' East of Pipeline
 Wit-S75W 17.07 8" Hemlock
 S55E 27.19 8" Hemlock
 N85E 22.65 8" Maple
 North 6.48 6" Hemlock

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-13: Found 1/2" x 18" capped iron and two 1972 witnesses, four 2-11-92 witnesses and four 9-15-92 witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-13: Set 5/8" x 36" roerd with Clare County Remonumentation Cap marked P.S.27458. Accepted as the best available evidence of the accepted position of the corner.

Witnesses:
 N5W 16.27', nail & tag, 9" Spruce (OBT)
 N18E 6.37', nail & tag, 8" Spruce (OBT)
 S53E 27.17', nail & tag, 10" Spruce (OBT)
 N86E 22.58', nail & tag, 10" Maple (OBT)



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul A. Lapham
 Date 9-8-98

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-16-98