

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 A D
 # 58-94
 94 NOV 28 AM 10:37

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 6W	1-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 COLEMAN, G.L.O. POST WIT.-(1)SPRUCE PINE 9" N35 1/2"W 24 LKS. (2)SPRUCE PINE 8" S56"E 27 LKS. C.S.R. L.6, PG.255 WIT.-(3)Y. PINE 16" N76 1/2"W 12 LKS. (4)FENCE POST 8" S25"E 36 LKS. 6-23-06 A. JOHNSON, C.S.R. L.4, PG.61 WIT.-(4)FENCE POST S25"E 36 LKS. (5)NORWAY PINE 16" N36 1/2"W 12 LKS.	8-16-33 A. JOHNSON C.S.R. L.2, PG.54 WIT.-(6)OAK 4" S47"W 116 LKS. (7)OAK 6" N47"W 128 LKS. NO RECORDED SURVEYS 6-21-74 MCCLUNG, L.C.R.C. #193 1/2" PIPE FOUND WIT.-(8)4" R. OAK N20"E 68.15' (9)8" R. OAK S40"E 56.80'
---	--

3-30-89 ROSER, L.C.R.C. #577
 1/2" PIPE
 WIT.-(8)10" R. OAK N20"E 67.91'
 (9)10" R. OAK S30"E 56.27'
 (10)7" R. PINE S45"E 39.45'
 (11)6" R. PINE S50"W 48.96'
 (12)CEDAR POST N45"W 50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x2' PIPE. EXCAVATED TO 3'. FOUND NO OTHER EVIDENCE.
 FOUND WITNESSES # 8,9,10,11, & 12.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Toph
 Date Nov 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN GRAVEL ROAD.

WITNESSES:
 N20"E 67.91' - NAIL & TAG - 12" R. OAK (8)
 S40"E 56.80' - NAIL & TAG - 12" R. OAK (9)
 S50"E 39.45' - NAIL & TAG - 8" R.PINE (10)
 S50"W 48.96' - NAIL & TAG - 8" R. PINE (11)
 N45"W 50' - NAIL & TAG - DNR MARKER (12)

Signed by Mark R. Robison Date 11-23-94
 Surveyor's Michigan License No. 27458