

CLARE County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R06W T19N R06W T R T R	I-13 I-1
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

RECEIVED  
E 14  
#292-98  
98 NOV 18 AM 9:57  
REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. MAULAY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R06W I-13 and T19N, R06W I-1

A. Description of original monument and accessories and/or subsequent restoration:

I-13: 1838 Nicholson  
Set Post Cor Sec 34 & 35  
Wit-W. Pine 16 N22W 21  
W. Pine 15 N84E 25

12-15-76 Ostling LCRC#277&Plat of Survey  
Set Cor on line between Section Corner East & MC West for latitude and on line over 1/4 & Section Corner North between 34 & 35 for departure. Set DNR Monument  
Wit-East 16' Red Top Post  
N50E 39.55 7" J. Pine  
N65 26.75 4" J. Pine

9-15-92 Gourdie-Fraser File Drawing  
References Corner Meas West 2618.09 to 1/4 Corner (DNR is 2618.70)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13: Found DNR Monument and two witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: Accepted DNR Monument as Clare County Remonumentation Monument. Accepted as best available evidence of the proper method of re-establishment of the corner.

Witnesses:  
N65E 26.75', nail & tag, 6" J. Pine (OBT)  
East 15.15', nail & tag, Red Top Cedar Post (OBT)  
N45E 51.60', nail & tag, 11" J. Pine  
N49W 81.93', nail & tag, 13" Oak  
West 64.91', nail & tag, 13" Oak



APPROVED LAND CORNER  
P.A. 845 of 1980  
Clare County  
Chairman Paul S. Leph  
Date 9-8-98

Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 11-16-98

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION