

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 EVID AD
 # 55-94
 94 NOV 28 AM 10:37

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

CLARE
 (County)

Located In:

Corner Code ##

- | | | | | | |
|---------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>20N</u> | R | <u>6W</u> | <u>J-7</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 COLEMAN, G.L.O.
 POST
 WIT.-(1)SPRUCE PINE 8" N32 1/2°W 11 LKS.
 (2)SPRUCE PINE 6" S52°E 17 LKS.

C.S.R. NONE

NO RECORDED SURVEYS

6-28-76 OSTILING, L.C.R.C. #282
 SET DNR MONUMENT BY PROPORTIONATE MEASUREMENT
 WIT.-(3)4" J. PINE S30°W 34.45'
 (4)4" J. PINE N40°W 54.80'
 (5)CEDAR POST NORTH 30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MARKER, CAP HAD BEEN BROKEN, SO WE REMOVED. EXCAVATED TO A DEPTH OF 3'.
 FOUND NO OTHER EVIDENCE.
 WE FOUND WITNESSES # 3 & 4.

APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman Paul B. Sopher

Date Nov 23, 1994

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN GRAVEL ROAD.

WITNESSES:
 S30°W 34.45' - NAIL & TAG - 6" J. PINE (3)
 N40°W 54.80' - NAIL & TAG - 7" J. PINE (4)
 N25°E 41.85' - NAIL & TAG - 6" J. PINE
 S05°W 31.8' - NAIL & TAG - 10" J. PINE



Signed by Mark R. Robison

Date 11-23-94

Surveyor's Michigan License No. 27458