

RECEIVED
 E 10 AD
 # 61-94
 94 NOV 28 AM 10:36

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>20N</u> R <u>6W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. GARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 COLEMAN, G.L.O. PG.528 POST WIT.-(1)SPRUCE PINE 8" N48°E 7 LKS. (2)SPRUCE PINE 10" S44°W 28 LKS.	9-7-84 LAPHAM, L.C.R.C. #458 DNR MONUMENT WIT.-(5)N45°E 42.26' 10" JACK PINE (6)S40°E 38.30' 10" R. PINE (7)N45°W 41.22' 10" JACK PINE (8)S45°W 41.49' 14" OAK
8-16-33 A. JOHNSON, C.S.R. L2-PG.53 WIT.-(3)OAK 6" N36°W 77 LKS. (4)OAK 10" N81°30'E 100 LKS.	NO RECORDED SURVEY
6-18-76 OSTLING, L.C.R.C. #283 SET DNR MONUMENT OVER 1 1/4" PIPE WIT.-(5)5" J. PINE N43°E 42.05' (6)5" R. PINE S33°E 38.05'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MARKER, 1"x2" PIPE WITH CAP. CAP WAS BROKEN OFF, SO WE REPLACED MARKER WITH 5/8"x36" MON. WITH 3" CAP.
 FOUND 1 1/2"x14" PIPE BELOW DNR MARKER. EXCAVATED DOWN TO 4'. FOUND NO OTHER EVIDENCE.
 FOUND WITNESSES #5, 6, 7, & 8.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul B. Lephem
 Date Nov. 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:
 N45°E 42.26' 12" J. PINE - NAIL & TAG (5)
 S30°E 38.30' 16" R. PINE - NAIL & TAG (6)
 N45°W 41.22' 10" J. PINE - NAIL & TAG (7)
 S45°W 41.49' 17" R. OAK - NAIL & TAG (8)



Signed by Mark R. Robison

Date 11-23-94

Surveyor's Michigan License No. 27458