

RECEIVED  
 E 10 A 0  
 # 62-94  
 94 NOV 28 AM 10:36

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 20N R 6W M-7  
 T 20N R 5W A-7 (COMMON CORNER)

2. Property Controlling in Section

S T R  
 S T R

3. Miscellaneous Property in Sec.

S T R  
 S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1856 COLEMAN, G.L.O. PG.517  
 POST, (20" WHITE PINE FOR COR. IS GONE)  
 WIT.-(1)SPRUCE 8" N50°W 327 LKS.

8-16-33 A. JOHNSON, C.S.R. L.2-PG.53  
 WIT.-(2)Y. PINE 20" S26°30'E 189 LKS.  
 (3)Y. PINE 18" N52°W 241 LKS.

NO RECORDED SURVEYS

7-28-76 OSTLING, L.C.R.C. #279  
 FOUND 3/4" BAR, SET DNR MONUMENT  
 WIT.-(4)12" R. OAK N64°E 66.5'  
 (5)24"R. PINE N28°W 164.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MONUMENT. 3 1/4" CAP ON 1" PIPE IN GOOD CONDITION. FOUND WITNESSES # 4 & 5.  
 EXCAVATED DOWN 2' AROUND MONUMENT. NO OTHER EVIDENCE.

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul B. Pappas

Date NOV 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCEPTED DNR MONUMENT 3 1/4" CAP ON 1" PIPE:  
 WITNESSES:  
 N64°E 66.5' 16" R. OAK - NAIL & TAG (4)  
 N28°W 164.87' 28" R. PINE - NAIL & TAG (5)  
 S35°E 118.7' 32" STUMP WITH CLUSTER OF 3" TREES - NAIL & TAG  
 S45°W 43.5' 18" J. PINE - NAIL & TAG



Signed by Mark R. Robison

Date 11-23-94

Surveyor's Michigan License No. 27458