

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <input checked="" type="radio"/> R. <u>6</u> W. <input checked="" type="radio"/>	<u>J-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>20</u> N. <input checked="" type="radio"/> R. <u>6</u> W. <input checked="" type="radio"/>	<u>14; 15; 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. <input type="radio"/> S. <input type="radio"/> R. _____ E. <input type="radio"/> W. <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 18, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

16

Set 5/8"x36" iron bar & red-top post		
15" B. Cherry	S37°E	23.8
14" B. Cherry	N81°W	34.8

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-3 Set by proportionate measurement midpoint on line between section corners. No previous corner.
- 14 Set by standard survey procedure for subdivision of sections.
- 15 Set by standard survey procedure for subdivision of sections.
- 16 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3	14	15
Set DNR mon. & red-top post	Set 1/2"x36" iron bar &	36" of 5/8" iron bar & red-top post
8" soft Maple (incluster)	red-top post	5" W. Pine N89°W 44.25
S18°E 37.45	2" W. Pine S43°W 59.2	5" B. Oak S52°E 26.55
14" Black Oak S48°W 70.2	10" W. Oak (in cluster)	
	S82°W 88.1	

SIGNED BY Kenneth J. Ostling

DATE June 29, 1976

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CLARE COUNTY