

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. R. <u>6</u> W.	J-5; J-7
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>20</u> N. R. <u>6</u> W.	1; 7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restorations:~~

C. (continued)

7

Set 5/8"x3' hex. iron bar
and cedar post
3" J. Pine N79°E 17.8
8" R. Oak S03°W 21.95

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-5 Found 1 1/2" pipe in old E-W trail road, probably established in old county survey. Old NBT stump NE.
- J-7 Set by proportionate measurement, midpoint on line, between section corners. Could find no previous corner.
- 1 Set by standard survey procedure for the subdivision of sections.
- 7 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5	J-7	1
Set DNR mon. & red-top post	Set DNR monument	Set 5/8"x3' of hex. rod & cedar post
7" W. Oak N82°E 27.1	4" J. Pine S30°W 34.45	4" Maple N78°W 20.45
7" Maple N02°W 31.25	4" J. Pine N40°W 54.80	10" Oak N65°E 23.35
	Cedar Post North 30'	

SIGNED BY Kenneth J. Ostling DATE July 28, 1976

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CLARE COUNTY