

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CLARE
(County)

Located In: _____ Corner Code ##

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------------|
| 1. Public Land Survey | T | <u>20N</u> | R | <u>6W</u> | <u>I-1, J-1,</u> |
| | T | _____ | R | _____ | <u>K-1</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | <u>2</u> | T | _____ | <u>I</u> |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL F. ROSER, in a field survey on JANUARY 29, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	J-1	K-1	I
FD 1 1/4" PIPE FOR NW COR SEC 2. PIPE FITS WITS OF RECORD BY LS, P. LAPHAM, 1973 & WAS USED BY LS, J. KNAPP IN 1988 CERT OF SURVEY. COR FALLS BETWEEN N-S TRAIL ROADS, 66' E & 87' W. SE EDGE CLAM RIVER IS WEST 183' (± 10').	REESTABLISHED N 1/4 COR OF SEC 2 ON LINE & MIDWAY BETWEEN REESTABLISHED NE & FD NW COR'S OF SEC 2. COR FALLS IN WILLOW BRUSH SWAMP (1 1/2' OF WATER). NO AVAILABLE WITS.	REESTABLISHED NW COR SEC 1, ON LINE BETWEEN FD NW COR SEC 2 & CALC SE COR SEC 36, T21N-R6W; AND PROPORTIONATE MEAS TO LS, J. KNAPP 1988 SURVEY DATA. COR FALLS IN SWAMP, 2 1/2' ± OF WATER.	ESTABLISHED THE NE COR OF LOT 4 OF FRL NW 1/4 OF SEC 2 (PER 1856 GLO PLAT, RUN-OUT SEC TO MICH 2ND CORR LINE), PER STANDARD BLM INSTRUCTIONS. COR FALLS IN WILLOW SWAMP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1	J-1	K-1	I
FD 1 1/4" GALV PIPE; ADDED CED POST W/LOC TAG. *12" R PINE N60°W 23.27' **3" W PINE N50°E 11.13' *13" W BIRCH S75°E 28.56' **5" W PINE S50°E 8.45' *12" R PINE S05°E 35.58'	PUSHED IN 1" X 96" GALV PIPE W/ALUM DNR CAP. CTR N-S TRAIL RD (ON RIDGE OF HIGH GROUND) EAST 476'	PUSHED IN 1" X 144" GALV PIPE W/ALUM DNR CAP. 4" TAMARACK N65°W 47.3' 6" DEAD TWIN TAMARACK S80°E 22.5' 2" TAMARACK S20°W 45.6' 3" TAMARACK S35°W 47.8'	PUSHED IN 1" X 96" GALV PIPE W/RLS CAP & CED POST W/LOC TAG. W. EDGE SWAMP WEST 800' ± NO OTHER WITS AVAILABLE.

*RLS P. LAPHAM WITS
 **WIT BY OTHERS.

Signed by Carl F. Roser 12-02-92 Date _____
 Surveyor's Michigan License No. 12028

