

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION SW CORNER OF SECTION 6, BATH TWP.

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Clinton
(County)

Located In: Corner Code #/

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>5N</u> R <u>1W</u> | <u>A-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED

LIBER 4, PAGE 36

DEC 12 11 59 AM '94

REGISTER OF DEEDS
CLINTON COUNTY, MICH.

Arden S. Pierson

Register of Deeds Stamp & File Number

Arden S. Pierson PS, in a field survey on March 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 - ORIGINAL SURVEY BY HARVEY PARKE, DS, 1826 survey by Chas Hollister, County Surveyor, in a survey of the W $\frac{1}{2}$ of NW frac. 1/4 of Section 7, in October 1879. Found stone set and found DeWitt corner from old witnesses and this was at proper distance. (51 links (33.66') south of standard corner.

R.H. Colburn, County Surveyor, in a survey of Section 6, T5N, R1W, in December of 1883, found stone set with witness: 8" Elm -S84°E- 220.5 links (145.53')

* (SEE BACK OF SHEET)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 6, Bath Township

A-3 - Found 1/2" rod & cap - 1/2" rod & cap -North- 33.72' And is accepted as a careful and faithful reestablishment of the position of the original corner. Removed 1/2' rod and Set Standard Clinton County Monument and monument box - set 4" below lip of mon. box - placed rod next to monument. Verified position from Land Corner Recordation Certificates.

APPROVED BY
CLINTON COUNTY PEER GROUP
DATED 11/9/94
J. 709

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 (SW corner Section 6)
Clinton County Monument

Face concrete anchor post -N20°W- 66.46'
Nail & tag SW face power pole -N51°W- 180.05'
Nail & tag NW side 14" Oak -N61°E- 74.87'
Nail & tag SW side 30" Maple -S59°E- 77.75'

*Standard Clinton County Monument is a 2 $\frac{1}{2}$ " dia. steel tube 30" long with a stamped brass cap and breakaway magnetic base.

NOVEMBER 1, 1994

Signed by *Arden S. Pierson*

Date

Surveyor's Michigan License No. 13039

Recorded in Liber 2, page 71, by Ronnie M. Lester, dated July 26, 1976. "Excavated at this location in search of stone as set in survey in 1879 by Charles Hollister, County Surveyor. Did not find stone or accessories as called for. Set 1/2" bar & cap on town line at centerline of road to East. Distances North & South in close accord with prorated measurements of original government measurement." With Witnesses:

"X" scribed in top of concrete post -NW- 67.21'
Nail & tag in SE side 26" Oak -WSW- 68.99'
Nail & tag in N. side 24" Maple -SE- 77.75'